IMPORTANT

THE DIGITAL FILE FOR
THE INSERT(S) OF THIS REPORT
HAS BEEN PLACED IN HSD8
SUBDIRECTORY SMOOTH
DIRECTORY COLORSS AS:
F00206_1 AND F00206_2
THE FILE SIZE IS TOO LARGE
FOR HSD2 SUBDIRECTORY DR.



Diagram No. 1207-2

NOAA FORM 76-35A

U.S. DEPARTMENT OF COMMERCE
NATIONAL OCEANIC AND ATMOSPHERIC ADMINISTRATION
NATIONAL OCEAN SURVEY

DESCRIPTIVE REPORT

(HYDROGRAPHIC)
Type of Survey . Wire Drag Field No
LOCALITY
State Massachusetts
General Locality Cape Ann to Boston
Locality
19 ₆₆ CHIEF OF PARTY C.H.Nixon
LIBRARY & ARCHIVES
DATEJune 20, 1967

☆ U.S. GOV. PRINTING OFFICE: 1976-669-441

NOTE: A new system for registering Field Examinations (FE's) was established in 1980. All FE's are now consecutively numbered as shown hereon. The date shown in the new format is the actual date of survey. This material was previously registered as;

FE No.2 1967WD

FENO.2 1967 WIRE DRAG

Diag. Cht. No. 1207-2.

WIRE DRAG

FORM C&GS-504						
U.S. DEPARTMENT OF COMMERCE ENVIRONMENTAL SCIENCE SERVICES ADMINISTRATION COAST AND GEODETIC SURVEY						
DESCRIPTIVE REPORT						
Type of Survey Wire Drag						
Field No. OPR-466 Office No. F.E. No. 2 ((1967) W.D.						
LOCALITY						
State Massachusetts						
General locality Cape Ann to Boston						
Locality						
1966						
CHIEF OF PARTY						
C. H. Nixon						
LIBRARY & ARCHIVES						
DATE June 20, 1967						

USCOMM-DC 37022-P66

Note:

Three sections of chart accompany this report.

DESCRIPTIVE REPORT

WIRE DRAG INVESTIGATIONS

F.E. NO. 2, 1967 W.D.

PROJECT OPR-466

CAPE ANN TO BOSTON, MASS.

1966

CHARLES H. NIXON - CHIEF OF PARTY

A. AUTHORITY:

Instructions dated January 12, 1966 and Additional Items dated June 10, 1966.

B. CHARACTER AND LIMITS OF THE WORK:

Investigation of certain shoals, obstructions and wrecks charted / (C&GS charts 240 & 246) from the vicinity of Cape Ann to Boston, Massachusetts for chart revision purposes.

C. CONTROL AND SHORELINE:

The investigations were carried out on the largest scale charts in the area.

All control was visual, utilizing charted objects as signals.

D. DATES OF SURVEY:

Field work began on 27 April 1966 and terminated on 30 June 1966.

E. VESSELS AND EQUIPMENT:

The wire drag vessels WAINWRIGHT & HILGARD acted as guide and end launch respectively. HILGARD's skiff was used as tender.

LIST OF INVESTIGATIONS

OPR-466 Cape Ann to Boston, Mass.

Item #12: cht. 240

The 36 ft. obstruction (not charted) in Lat. 42°27.54', Long. 70° 47.75" was not found. The major part of a one mile diameter circle was investigated on "U" day (May 31, 1966) at an effective depth of 105 feet. The northeast and southwest edges of the circle were investigated on "DA" day (June 21, 1966) at effective depths of 89 and 86 feet respectively. The existence of the 36 ft. sounding in the vicinity of the above position has been disproven and it is recommended that it not be charted.

Item #13: chf. 240 √

The 50 ft. obstruction (not charted) in Lat. 42°27.65°, Long. 70° 49.50° was found at Lat. 42°27'(27.3)°, Long. 70°49'(27.8°...° Its least depth as determined by fathometer was 64.5 feet (pos. 10V).* This obstruction was cleared from two directions with an effective depth of 52.0 and 53.5 feet.

Five other obstructions were hung during this investigation. The general area is very rocky (as charted). All hangs are considered rocks and should be charted as such. All data concerning these hangs may be found in the Hang and Clear Data. (Attachment No. 4).

It is recommended the obstruction be charted as a pinnacle rock at the above position and shown as cleared by 5% feet.

CONCUR.

Item #14: Ch/ 240

The <u>submerged_wreck PA</u> charted in Lat. 42°27.50', Long. 70°54.41' was not found. The wreck symbol was cleared with an effective depth of 26.0 feet going west and 23.5 feet going south. The area 1 mile south, southeast and southwest of the wreck symbol was investigated generally at depths from 5 to 10 feet off the bottom. The only trace of a wreck found was a piece of plywood which was picked up in the drag. It was impossible to tell where the section of the wreck was originally encountered. The wreck does exist but the opinion is that it is so broken up that it is no longer a hazard to navigation.

Three uncharted soundings were located during this investigation.

Least depths were determined by divers and checked with hand lead soundings. The first was at Lat. 42°27'35", Long. 70°54'27" at a NM 16 least depth of 16.8 feet. The second was at Lat. 42°27'29", Long. 70°54'45" at a least depth of 18.5 feet as determined by fathometer.*

*Fathogram attached

ROCK (per chart letter #953/11)

Item #14 (cont.): chf. 240

Divers searched the area near the fathometer sounding and determined a 23.5 foot sounding on a <u>rock</u> which was checked by a hand lead sounding. There was two to three feet of thick kelp on the <u>rock</u>. The shoaler sounding by fathometer is probably the result of the thick kelp growing on top of the rock. It is estimated that the controlling depth is 20 feet. The area around this sounding could not be cleared because of lobster pots in and around the sounding. The third (29EA) is located at Lat. 42°27'24", Long. 70°54'05" at a least depth of 26.7 feet.* It was identified by divers to be a large boulder.

It is recommended that the wreck symbol be removed from the chart and the isolated soundings obtained be charted as such. SEE REVIEW

Item #16: c//t. 246 #240

The wreck cleared by 45 ft. charted in Lat. 42°23.36', Long 70°55.19' was hung on "S" day (May 26, 1966) at the charted position. Using the fathometer, the least depth was determined to be 47.0 feet.*

The wreck was cleared on the same day with a drag from north to south at an effective depth of 45 % feet. Divers stated that a drag from south to north would probably slide over the smooth surface of the wreck.

It is recommended that no change be made in the existing charts.

position shown on field examination.

Item #17: chts. 240 \$ 246

The 41 ft wreck PD charted in Lat. 42°23.78', Long. 70°51.76' was located at Lat. 42°23'41", Long. 70°51'52" at a least depth of 55 % feet (Divers L.L.).

The wreck was subsequently cleared by 57.8 and 54.8 feet from opposite directions.

It is recommended the wreck be charted at the above position and shown as cleared by 55 feet.*

Item #18: cht. 246

The <u>submerged wreck PA</u> charted in Lat. 42"21.03', Long. 70°56.00' was not located. The wreck symbol was cleared in two directions at effective depths of 37% and 36.% feet. The North Channel between buoys R "2" and "11" was extensively investigated at depths ranging from 33 to 41 feet.

Several obstructions were found on the first investigation of this area at depths from 34 to 36 feet. The Army Corps of Engineers were

* Fathogram attached

Accept fath Ship on preceding

<u>Item #18 (cont.):</u>

N.M. #36/66

informed of these obstructions and subsequently removed a number of boulders from the eastern side of the North Channel to President Roads between buoys "5" and "7". The Corps of Engineers now claims a controlling depth of 38 feet for the eastern side of the channel. The eastern side was cleared with wire drag in two directions with 36.5 and 37.0 feet. Annattempt to drag at 37.5 effective depth resulted in a hang (See Strip 1-13C, hang 13C same as 26KA).

No boulders were removed from the western side and it has only been cleared with 33 feet from two directions.

The data concerning the ten obstruction located in the second investigation of North Channel may be found in the Hang and Clear Data.

As of June 29, 1966, it is recommended the eastern side of the channel be shown as having 36.5 feet controlling depth. the wreck symbol should be removed from the charts. In addition, BISTON NORTH CHANNEL TABULATION NOW SHOWS APPROPRIATE WIRE-DRAG CLETRANCES FOR CHANNEL (CHART 246, 122 ED. FEB. 24, 1919).

<u>Item #19</u>: chf. 246

The 19 ft. sounding (not charted) at Lat. 42°20.20', Long 70°56.26' was not found. The reported location of the 19 ft. sounding and the charted 20 ft. sounding 450 feet south of the 19 ft. were both cleared in two directions by 25.0 and 25.8 feet.

One hang was encountered in this investigation at Lat. 42°20'10", KNOWN Long. 76°56'23". It was hung at an effective depth of 28.0 feet SHOAL and later cleared in two directions by 27.0 and 27.5 feet.

On E day a pinnacle rock was located with fathometer near Item #19 and Buoy C:13", A least depth of 14.7 was determined at Lat. 42°20' 18", Long. 70°55'59". Fathogram is attached.

- CONCUR. DEW The 19 ft. sounding has been disproven and should not be charted. In addition, the non-existence of the 20 ft. charted sounding indicates an inadequacyoof the hydrography in the area and it is recommended that this area be incorporated in any future hydrographic survey.

20 ft ROCCONT **surkes**

REVIEW

Item #20: $^{\nu}$

The 24 ft. sounding (not charted) in Lat. 42°19.34', Long. 70°55.35' was not found. Its reported location was cleared in one direction with a 23 5 feet drag on "N" day (May 20, 1966).

Because of unfavorable drag conditions (narrow channel, strong current and the bottom contour), deeper drags would have resulted in The 24 ft. sounding was cleared by 23.5 feet.

The 24- Ft. from H-7719 WID. is considered to no longer Gof E. BP-70834-35 Aug. 1966, Do not Chart.

Item AD-1:

13" The reported obstruction in the area of 3½ Fathom Ledge, Lat. 42° 21'15", Long. 70°50'45" was not found. An extensive area ranging from 1 mi. N and 1 mi S of the ledge was covered with strips ranging from 40 to 65 feet effective depth. The least depth at 3½ Fathom Ledge was found to be 21.% feet (pos. 2T).* The area around the ledge was cleared by wrapping the buoy with drags set at 18.5 and 21.5 feet.

except one Some hangs were encountered but allawere on known soundings. data concerning there may be found in Attachment No. 4 (Hang and Clear Data). There is some doubt on the position of hang 39L. At processing the time of the hang it was noted that the hang was on a known 65' sounding. However, in smooth plotting the buoy cuts indicate a hang in 90 feet of water. It is believed that the hang was on a known shoal and that some error was made in recording. Both the shoal and indicated hang were cleared by 57.2 feet.

AND FOUND TO FALL ONKARAN 65 Ft. SOUNDING.

The reported obstruction has been disproven and should not be charted. CONCUR.

* Fathogram attached

The wrecks of two barges were located on Chart 246 south of Gallops Island in the vicinity of Lat. 42° 19' 27" Long. 70° 56 20"

A visible wreck, a rock awash, and a row of piling were located on Chart 246 east of Squantum in the vicinity of Lat. 42° 17' 57", Long. 71°00'05".

TIDE NOTE FOR HYDROGRAPHIC SHEET

November 27, 1967

Nautical Chart Division: R.H. Carstons

Plane of reference approved in 17 volumes of sounding records for Wire Drag FE NO. 2, 1967

HYDROGRAPHIC SHEET

Locality: Cape Inne to Boston, Massachusetts

Chief of Party: C.H. Nixon (1966)

Plane of reference is mean low water

Tide Station Used (Form C&GS-681): Boston, Massachusetts

at the working grounds Height of Mean High Water above Plane of Reference, is as follows:

9.0 feet

Remarks Tide reducers for the following positions have been revised in red and verified.

Vol. Positions

Chief, Tides and Currents Branch

U\$COMM-DC 6680-P64

FORM C&GS-946 (REV. 11-65) (PRESC. BY HYDROGRAPHIC MANUAL 20-2, 6-94, 7-13)

U.S. DEPARTMENT OF COMMERCE ENVIRONMENTAL SCIENCE SERVICES ADMINISTRATION COAST AND GEODETIC SURVEY NAUTICAL CHART DIVISION

HYDROGRAPHIC SURVEY NO. F.E.No.1-1967 W.D.

RECORDS ACC	RECORDS ACCOMPANYING SURVEY: To be completed when survey is registered.									
RECOR	RECORD DESCRIPTION AMO						RECORD DESCRIPTION			
SMOOTH SHEET	SMOOTH SHEET 2					HEET	s			5
DESCRIPTIVE RE	PORT				OVERL	AYS	(Miscel	laneo	us)	l- Envelope
DESCRIPTION	DEPTH RECORDS	HORIZ. C		PRINT	routs	TA			D CARDS	ABSTRACTS/
ENVELOPES	1									
CAHIERS										
VOLUMES	17									
BOXES								<u> </u>		
T-SHEET PRINTS	(List)									
SPECIAL REPOR	TS (List)				'					
	•									
			DEFICE	PROCES	SING AC	TIVIT	TIFS			
	The following st							rt on the	survey	
				AMOUNTS						
PR	OCESSING ACTIV	/ITY		PRE- VERIFICATION		VERIFICATION RE		REV	EVIEW TOTA	
POSITIONS ON SHEET								93.		
POSITIONS	CHECKED						313		***************************************	
POSITIONS	REVISED						3		,	
DEPTH SOUNDIN	IGS REVISED	depths	to ct	vo de	ag .			i		
	IGS ERRONEOUSLY		TPV	7364.						,
SIGNALS ERRON	IEOUSLY PLOTTED	ORTRANS	FERRED				•			
						<u> </u>	TIME (MA	NHOURS	;)	<u> </u>
TOPOGRAF	PHIC DETAILS			1				T		
JUNCTIONS									 	
VERIFICA.	TION OF SOUNDING	SFROM					1 hr.	 		
SPECIAL ADJUSTMENTS PIO HELD				ere w	K plot.		40 hrs	Ĭ		
ALL OTHE	Follow	Ad.D	Sheet.	had	+	-	tzethrs	T	L	
722 07112	TOTALS	nstruci	recl	 			165 hrs.		hrs.	
PRE-VERIFICATION BY						INNING DATE		ENDING	DATE	
								<u> </u>		
VERIFICATION E	VERIFICATION BDale E Walter					BEG	4/1/62	<u> </u>	ENDING	3/68
REVIEW BY	0.0	1/1/	the	-/	-	BEG	INNING DATE	Ē	ENDING	DATE
	valuz?	1/4	yes	<u> </u>		<u> </u>	5/6/68		5	13/68 COMM-DC 36271-P68

HANG AND CLEAR DATA

Remarks	Obstruction '	Boulder	Obstruction'	Chart at 55.5 obstruction	Obstruction *	Obstruction	Obstruction	Obstruction	Obstruction	Obstruction Obstruction	Obstruction	Pick Obstruction	
Cleared Effective Depth	52.01	56.01		57.01	52.0.	7.4.5 8.4.6.6			d do	opt.	****	## ##	
Sounding	•	56.01	25.0	***	*	• • •	m.I	ı	, `	34.0	1	1-18" day	tender
			62.01 3			39.0.	38.	38.81	38.81	•	38.	34.8	
Latitude Longitude	12°27' 13.8 " 70°49' 52 '4"	70.49,49.01	42°28'13.9" 70°49'39.6"	70.49132.51	42°27' 50.6 " 70°49'2 <u>4.</u> 0"	42°20'57"	42°21'01"/	42°21 101 11°7070°56 102 11°	70°56'04"	70°56'08"	12°21'02''	70.56.01"	
Position & Day Letter	100	160,	160	7FA"	, №8	8GA	246# 246#/ 26#7:	6на	12HA	of the second	2, HA	273A	
Chart No.	240	540,	240	240	240	546	246°	546	246	546	246	246	
Presurvey Review Item	13	13,	13	13 🖍	13 /	18 /	18	9	18,	18	18	18,	

HANG AND CLEAR DATA

Remarks	ARCO wreck	ROMANCE wreck	Grounding Knows Stork	Grounding 🗸	Crounding Keevel 546AC	Position not definite, grounding Known Store	Grounding Knew Stort	Grounding Known S 40P	Grounding Knows Stork	Groundi ng Known Stort	Grounding Kniew Stork	Rock
Effective Depth		54.00		10-44	15.00	10 th	44	46.54	15.55	- 14 CC		53.00
Sounding	**.0.24	55.	t	ı	ı	ı		1	1	1	i	56, s
Effective Depth	55.01	57.00	10.85	14. 3d	++-5.	15-49	\$	4	0	₹ †	10.16	60.00
Latitude Longitude	70.55.06.04	42°23'41" 70°51'52"	"5-50-10; "01-02-24	42°21'26" 70°50'58"	# 2021-11 " 7 00-50138 "	420201 " "610302#	15051 103 u	# 80,15,08 # 80,15,08	" \$1,13,05 "	42°21'12" 70°50'39"	164,0500L	12°27' 37.3 " 70°49' 27.6 " 1ched 2%
Position & Day Letter	228	21н 56ра	12	24K	######################################	*	40+	306	8	-362	#	10V 42°? 70°1 Fathogram attached
Chart No.	246	,972	9#2	546	9#2	## ##	446	9#4	9#2	9772	246	240′ ** Fat
Presurvey Review Item	16	17 /	16	AD-1 ~	*D-1	T-QV	40-1	***	40-1	*B-1	#	13 🖍

HAND AND CLEAR DATA

Remarks	Obstruction	Obstruction	Obstruction	A .ck	Boulder
Cleared Effective Depth	Not clanso	14 FE	37.0	00 E7	, \$
Sounding	i	ı	ı	38	24.0
Grounded- Effective Depth			37.81	, o.	26.0
Latitude Longitude	42°22°02" 70°55°29"	42°21'18" 70°55'53"	42°21°12" 70°55°5 % "	42°21'52° 70°55'30"	42, 27, 25"
Position & Latitude Day Letter Longitude	SKA .	23KA'	26KA~	4 00	14 BA
Chart No.	246	246	246	*	240
Presurvey Review Item	18,	18	18,	\$ -	, *

REVIEW

FIELD EXAMINATION NO. 2, 1967 W.D. WIRE-DRAG INVESTIGATIONS CAPE ANN TO BOSTON, MASS.

- 1. This wire-drag field investigation was made in compliance with instructions for Project OPR-466.
- 2. The purpose of the examination was to investigate and verify or disprove numerous reported wrecks and obstructions described in the Pre-Survey Review for Project OPR-466. A reported obstruction in the vicinity of Three and One-half Fathom Shoal was added for investigation by instructions dated June 10, 1966.
- 3. The results of the several investigations are shown on the accompanying sections of Charts 240 and 246. These chart sections are supplemented by six tracing cloth overlays inserted in the Descriptive Report.
- 4. A comparison between the field examination and the charts of the areas in which work was done indicates that advance information was used for charting in several instances. Certain revisions to the charts are necessary to reflect the final results of this field examination.

Attention is directed to the following:

CHART 240 - 9th ED., Jan. 22, 1968

P.R. Item No. 12 - Correctly charted.

P.R. Item No. 13 -

- A. The <u>cleared by 51 ft</u>. presently charted in lat. 42°27'38", long. 70°49'28" should be changed to a cleared by 53 ft.
- B. The <u>52-ft</u>. sounding presently charted in lat. 42°27'43", long. 70°49'55" should be changed to a 60-ft. sounding.
- C. The cleared by 52-ft. presently charted in lat. 42°27"51", long. 70°49'23" should be changed to a cleared by 51-ft. in lat. 42°27'52", long. 70°49'23" (about 30 meters due north).

- D. The <u>cleared by 57-ft</u>. presently charted in lat. 42°27'56", long. 70°49'32" should be moved in position to lat. 42°27'57", long. 70°49'32" (about 30 meters due north).
- E. The cleared by 56-ft. presently charted in lat. 42°28'15", long. 70°49'48" should be shown as a cleared by 57-feet RK.
- F. The cleared by 57-ft. presently charted in √ lat. 42°28'13", long. 70°49'40" should be changed to a cleared by 58-ft.

P.R. Item No. 14 -

A. The 20-ft. sounding RK presently charted in lat 42°27'30", long. 70°54'44" should be changed to an 18-ft. sounding RK in lat. 42°27'29, long. 70°54'45".

NM33/68

- B. The cleared by 25-ft. WK presently charted in lat. 42°27'30", long. 76°54'25" should be changed to a cleared by 26-ft. WK.
- C. The 27-ft. sounding presently charted in lat. 42°27'25", long. 70°54'05" should be changed to a cleared by 24-ft RK.

 MM 33/68

CHART 246 - 32nd ED., Feb. 26, 1968

151

P.R. Item No. 16 -

- A. The cleared by 46-ft. Wreck presently charted in lat. 42°23'22", long. 70°55'11" should be changed to a cleared by 45-ft. Wreck in lat. 42°23'22", long. 70°55'09" (about 40 meters eastward).
- P.R. Item No. 17
 A. The cleared by 53-ft Wreck presently charted in lat. 42°23'41", long. 70°51'52" should be changed to a cleared by 54-ft. Wreck.

P.R. ITEM NO. 18

A. The first investigation of North Channel took place between April 27 and May 11, 1966. This investigation yielded eight groundings on rocks and obstructions. (A&D Sheet showing results of 1st investigation filed with records.)

N. to M. No. 36 of 1966 reported that the Corps of Engineers had removed the boulders in the East part of the Channel.

The second investigation of North Channel took place between June 7 and June 26, 1966. This investigation confirmed the removal of five boulders found during the first investigation, but shows nine other obstructions, some of which were located during the previous investigation. (A&D Sheet showing results of 2nd investigation filed with records.)

In all, ten obstructions remain in the channel. These obstructions have been plotted on a Combined A&D Sheet, filed in the Descriptive Report which shows the final results of the wire-drag operations in North Channel.

A Corps of Engineers survey of July 1966 (BP-70415), although it contains indications of most of the remaining obstructions, shows depths over them from 1-3 feet deeper than does this field examination. The tabulated controlling depths for North Channel now charted from this C. of E. survey conflict in part with depths shown on this field examination. However, the maximum wire-drag effective cleared depths obtained during this investigation have been charted as footnotes to the channel tabulation and are substantially correct.

A letter, with an overlay enclosed, showing the remaining critical obstructions has been sent to the Corps of Engineers (dated May 10, 1968) asking for additional information on these features. Until subsequent information is received, the charted footnote is believed to adequately portray the results of the investigation of North Channel.

The sunken wreck previously charted in the channel (the original subject of the investigation) is considered disproved and should not be charted.

P.R. ITEM NO. 19

A. The 14-ft. sounding presently charted in lat. 42°20'18", long. 70°55'59" is a pinnacle rock and should have the note Rk charted nearby.

B. The 20-ft. sounding presently charted in lat. 42°20'07", long. 70°56'17" is from H-2146 (1892). It was brought forward to H-6643 (1940), and although that survey showed depths of 26-ft. in the vicinity, the 20-ft. sounding was not considered disproved. The present field examination cleared the 20-ft. by a drag strip of 26-ft. thereby showing the prior sounding to have been faulty. The 20-ft. sounding should be deleted from the chart.

P.R. ITEM NO. 20

Correctly charted.

ADDITIONAL ITEM NO. 1

- A. The <u>cleared by 44-ft.</u> presently charted in lat. 42°21'26", long. 70°50'55" should be moved to lat. 42°21'26", long. 70°50'53".
- B. The 37-ft. sounding presently charted in lat. 42°21'02", long. 70°50'58" should be charted as having been cleared by 36-ft.
- C. The <u>20-ft.</u> sounding presently charted on Three and One-half Fathom Ledge in lat. 42°21'13", long. 70° //M33/67 50'45" should be charted as having been cleared by 18-ft.
- D. The <u>50-ft</u>. sounding Rk shown on the present field examination in lat. 42°20'51", long. 70°51'15" should be added to the chart.

ITEMS FOUND BY FIELD PARTY

A. The note <u>PA</u> referring to the two wrecks charted rear lat. 42°19'27", long. 70°56'21" should be deleted from the chart since the wrecks have been accurately located.

- B. The <u>visible wreck</u>, <u>row of piling</u>, and <u>rock awash</u> charted in the vicinity of lat. 42°17'56", long. 71°00'08" should be revised in position to agree with the positions shown on the field examination.
- 5. All Pre-Survey Review Items investigated were satisfactorily accomplished.
- 6. In smooth plotting this field examination, the field party omitted plotting several drag strips that were considered unnecgessary. It was difficult for the verifier to check this without first plotting the strips. Once plotted, however, some strips did contribute to the maximum effective cleared depth, and thus were retained.
- 7. In an area being investigated with many overlapping drag strips, an A&D sheet should be made showing the complete results of the investigation. The field party neglected to do this in three instances, causing additional work during verification.
- 8. The Descriptive Report adequately covers all other matters pertaining to this examination. No further discussion is considered necessary.

Reviewed by: Dale E. Westbrook 5/13/68 Inspected by: R.H. Carstens 5/21/68

RH Consteur

Approved by:

John O. Boyer

Chief, Marine Chart Division

checked for land correction 47. 4. 8-5-68

APPROVAL SHEET

The attached report, related wire drag records and plotting sheets have been inspected by me and are approved.

Charles H. Nixon
Lt. Commander, C&GS
Commanding, WAINWRIGHT
& HILGARD

$\underline{\mathtt{L}}\ \underline{\mathtt{I}}\ \underline{\mathtt{S}}\ \underline{\mathtt{T}}\ \ \underline{\mathtt{O}}\ \underline{\mathtt{F}}\ \ \underline{\mathtt{S}}\ \underline{\mathtt{I}}\ \underline{\mathtt{G}}\ \underline{\mathtt{N}}\ \underline{\mathtt{A}}\ \underline{\mathtt{L}}\ \underline{\mathtt{S}}$

Signal Name	Source
Name	
ALL	Pt. Alleston, Tower
AND	Deer Island Lighthouse
AMP	Swampscott, Standpipe
BAK	Bakers Island light, Alt. Fl W&R 15 sec, 111 ft. 17M HORN
CUP	Deer Island, Black Cupola
${ t EAT}$	Great Faun, Stone Beacon
EGG `	Egg Rock, 42°26'03", 70°53'49"
HAN	Nahant, church cupola
\mathtt{HIL}	Great Quincy, (Moonhead) Tank
JAC	Jack Pt. light, F G 130 ft. 15M
KEN	Hull, Radio Station, WBZ, E. Mast
KIN	Lynn, Stack, 42°28'15", 70°55'41"
LED	Dread Ledge, Beacon, 42°27'22", 70°53'43"
LEG	Marblehead Rock, tower
LIT	Boston Lighthouse
LON	Long Island Head Lighthouse (1902) F 120 ft. 17M
MAR	Marblehead, tower
MIN	Minots Ledge Lighthouse (1915)
MOS	Moses Hill, standpipe
NAN	Nantasket, Telegraph Hill, tower
NIX	Nixes Mate, BW Beacon
NUT	Quincy, Nut Island, Stack
PIP	Winthrop Head, standpipe
PIR RAV	Swampscott, spire
RAW	The Graves Lighthouse Hull, Strawberry Hill, tank
ROW	Narrows, Lighthouse
SEA	Chelsea, tank, 42°24'03", 71°01'51"
TOR	Lynn, High Rock Observatory
TUM	Squantum, tank
WAM	Swampscott, cupola
WER	Lynn Beach, N. tower, 42°27'20", 70°56'15"
WES	Long Island, stack

Volume Number	Day- <u>Letter</u>	<u>Date</u> 1966	Number of Positions	Statute <u>Miles</u>	Square N. Mi.
11111122223333344444485555666667778888	A B C D E F G H J K L M N P Q R S T U V W X Y Z A B C D E F G H J K L A L A L A L A L A L A L A L A L A L	4/29 4/23 55/12 55/12 55/12 55/12 55/12 55/12 55/12 55/12 55/12 55/12 55/12 55/12 55/12 55/12 55/12 55/12 55/12 55/12 55/12 56	27 13 16 19 19 33 23 29 20 20 20 21 21 21 23 23 24 29 20 20 20 20 20 20 20 20 20 20 20 20 20	25452981726 3797692607013699167437	0.38 0.44 0.13 0.08 0.082 1.00 1.95 0.71 0.78 0.125 0.1
		TOTALS	930	74.3	20.73

TIDE NOTE

Tidal data was furnished by the Washington Science Center for the standard tide gage at Boston, Massachusetts.

The following corrections were taken from Table 2 of the Tide Tables and applied to the indicated investigations:

- 1. Marblehead, Mass.: HW -02m -0.4; LW -06m 0.0 Items 12,13
- 2. Broad Sound, Nahant,
 Mass.:

 HW -Olm -0.5; LW -02m 0.0 Items 13,14,
 16,17,18,19
- 3. Boston Light, Mass: HW OOm -0.5; LW +Olm 0.0 Item AD-1
- 4. Lowell Island, HW +02m -0.4; LW +01m 0.0 Items 18,20 The Narrows:

F. TIDE STATIONS:

Tidal information was furnished by the Washington Office for the standard tide gage at Boston, Massachusetts. Tide reducers were computed using corrections taken from Table 2 of the Tide Tables.

See Attachment No. 2 for List of Corrections.

All soundings and effective depths are in feet at Mean Low Water.

G. DRAG TEST:

Test of the drag followed the method outlined in the manual.

H. CONTROL OF WIRE DRAG:

Standard dual control methods were used. Cuts to the end buoy and to the opposite vessel were taken immediately after the fix. The cuts were labeled plus (+) if the object was to the right of the signal used, and minus (-) if to the left. Length of towline was from the center of the wheelhouse to the end buoy in each case.

J. ADEQUACY OF THE SURVEY:

This survey is considered adequate within the limits of the investigated items. All items assigned to the drag vessels on this project were investigated.

The survey was aided by the use of SCUBA divers to investigate hangs and to obtain leadline soundings of least depths over obstructions. The survey was handicapped by not having a larger, radiotelephone equipped launch for use as SCUBA and wire drag tender.

K. COMPARISON WITH CHART:

See Attachment No. 4 for List of Hangs and Clears.

L. TIME:

Seventy-fifth (75th) meridian time was used throughout the survey.


M. LIST OF ATTACHMENTS:

- 1. Statistics
- 2. Tide Note

3. List of Signals
4. Hang and Clear Data
5. List of Investigations
6. For (**) overlays for Items #13, #14,
#18, and AD #1.

Respectively submitted,

Caroll D. North, ENS, C&GS





F.E. NO. 2, 1967 P.R. Item No. 19 Chart 246


SHIPS WAINWRIGHT & HILGARD OPR - 466 ITEM AD-1 CHART 246 SCALE 1:25,000 OUERLAY 1 + 1 \$2,7 30, 42° 22' Least depth on 3 Fathom Ledge 20 ft. Cleared by 18 ft.

70	KIN O	WAM		RIGHT / HILGARD EM 14
		PIR	70° 54′	
42° 28'				
WER.		1384	16 BA 17 BA	LED NEA
			250	
			○E96	
42° 26'		HAN		


•








BOSTON - NORTH CHANNEL
COMBINED A & D SHEET
Showing final results of
investigation of P.R. Item #18
Chart 246





RECORD OF APPLICATION TO CHARTS

FILE WITH DESCRIPTIVE REPORT OF SURVEY NO. F.E. No.1-1967 W.D.

INSTRUCTIONS

A basic hydrographic or topographic survey supersedes all information of like nature on the uncorrected chart.

Letter all information.
 In "Remarks" column cross out words that do not apply.
 Give reasons for deviations, if any, from recommendations made under "Comparison with Charts" in the Review.

240	11-0-17		
-	11-7-61	Dennis Romeshung	Part Before After Verification Review Inspection Signed Via Drawing No.
246	11-13-67	Fannie Pauses	Part Before After Verification Review Inspection Signed Via Drawing No.
1106	12-7-61	M H Theid	Part Before Verification Review Inspection Signed Via Drawing No.
1107	12-18-67	97: N Nac	Drawing No. applied Thru 1106
240	6/26/68	Hardd V. Haward	Full Pm Refer After Verification Review Inspection Signed Via Drawing No. 19
246	6/26/68	Haralet Hawani	Full Review Inspection Signed Via Drawing No. 44
1207	7/11/68	Hard " Howay	Full After Verification Review Inspection Signed Via Drawing No. Applied Thun Charte 240 #19
70	8/18	Clarence Misfelds	and 246 # 44
71	9/68	C. Misfeldt	Full Past Before After Verification Review Inspection Signed Via Drawing No.
1106	12-8-72	J. Bailey	Full Part Refore After Verification Review Inspection Signed Via Drawing No. 28 Fully Applied
1107	12-14-7	J. Baily	FULLY APPLIED
71	3-12-73	A Heeley	FULLY APPO AFTER VERIFICATION REVIEW AND INSPECTION

FORM C&GS-8352 SUPERSEDES ALL EDITIONS OF FORM C&GS-975

USCOMM-DC 8558-P63